
Copyright © 2017 Perkins+Will


PROVIDENCE TARZANA MEDICAL CENTER PATIENT WING EXPANSION




























2 ACCESSIBLE PARKING SIGN DETAILS

1" = 1'-0"







1 ACCESSIBLE ROUTE SIGN DETAIL

PROVIDENCE
Tarzana
Medical Center

PROVIDENCE
TARZANA MEDICAL
CENTER PATIENT
WING







SITE DETAILS

SHEET NUMBER

A02-05INCREMENT 2





O1 OVERALL FLOOR PLAN LEVEL 00

1/16" = 1'-0"

FLOOR PLAN GENERAL NOTES

FLOOR PLAN LEGEND

EXISTING PARTITION

1-HR FIRE-RESISTANCE RATED TEMPORARY CONSTRUCTION BARRIER


NOT IN SCOPE OF WORK

1-HOUR FIRE BARRIER

EXPANSION JOINT LOCATION

PROVIDENCE
Tarzana
Medical Center

PROVIDENCE
TARZANA MEDICAL
CENTER PATIENT




		TITLE
		Approve
		Checkei
Drawn		Author
Job Number 7150		715016
MARK	ISSUE	DATE
A	INC2_PH1-SEG 1B BACK CHECK	03/17/2017
В	INC2_PH2-SEG 2A BACK CHECK #01	07/14/2017

FLOOR PLAN LEVEL

SHEET NUMBER

A10-00



FLOOR PLAN GENERAL NOTES

FLOOR PLAN LEGEND

EXISTING PARTITION


1-HR FIRE-RESISTANCE RATED TEMPORARY CONSTRUCTION BARRIER

NOT IN SCOPE OF WORK

1-HOUR FIRE BARRIER

EXPANSION JOINT LOCATION

PROJECT **PROVIDENCE Medical Center PROVIDENCE** TARZANA MEDICAL **CENTER PATIENT**



EXPANSION JOINT LEGELND

SEE SPECIFICATIONS AND TYPYCAL EXPANSION JOINT DETAIL ON A51-03

- 1 FLOOR TO FLOOR EXPANSION EJ INT F 02 \langle 2 \rangle FLOOR TO WALL EXPANSION - EJ INT FW 02
- (3) WALL TO WALL EXPANSION EJ INT W 02 4 WALL TO CORNER EXPANSION - EJ INT WW 02

$\left\langle \cdot \right\rangle$	WALL TO CEILING EXPANSION - EJ	INT WC 01
$\langle i \rangle$	CEILING TO CEILING EXPANSION -	EJ INT CC

FLOOR PLAN LEVEL

715016

Approver TITLE

B INC2_PH2-SEG 2A BACK 07/14/2017 CHECK #01

1 INC2_PH2-SEG 2A 04/20/2017
A INC2_PH1-SEG 1B BACK 03/17/2017
CHECK
MARK ISSUE DATE


SHEET NUMBER


A10-01 **INCREMENT 2**

Copyright © 2017 Perkins+Will

OVERALL FLOOR PLAN LEVEL 01


1/16" = 1'-0"







2 SOUTH ELEVATION

1/16" = 1'-0"











INC2_PH2-SEG 2A BACK CHECK #1	07/14/2017	
ISSUE	DATE	
Job Number		
Drawn		
Checked		
ved	Approver	
	TITLE	
	CHECK #1 ISSUE umber	

EXTERIOR ELEVATIONS

SHEET NUMBER


A20-02INCREMENT 2





PROVIDENCE
Tarzana
Medical Center

PROVIDENCE
TARZANA MEDICAL
CENTER PATIENT
WING




2	INC2_PH2-SEG 2A BACK CHECK #1	07/14/2017
MARK	ISSUE	DATE
Job Number 7150		
Drawn		Author
Checked		Checker
Approved		Approver
		TITLE

EXTERIOR ELEVATIONS


SHEET NUMBER


A20-03INCREMENT 2



PROVIDENCE
Tarzana
Medical Center

PROVIDENCE
TARZANA MEDICAL
CENTER PATIENT
WING






ENLARGED PARTIAL BUILDING ELEVATION


SHEET NUMBER

A30-05INCREMENT 2



PROVIDENCE
Tarzana
Medical Center

PROVIDENCE
TARZANA MEDICAL
CENTER PATIENT
WING





Α	MARK	ISSUE	DATE
	Job Numbe	er	715016
	Drawn		Author
	Checked		Checker
	Approved		Approver
			TITLE


ENLARGED PARTIAL BUILDING ELEVATION


SHEET NUMBER

A30-06INCREMENT 2









Job Numb	er	
Drawn		Author
Checked		Checker
Approved		Approver
		TITLE


EXTERIOR EXPANSION JOINT VIEWS

SHEET NUMBER

A32-03INCREMENT 2


PROVIDENCE TARZANA MEDICAL CENTER OSHPD SITE UTILITY MAKE-READY














CODE COMPLIANCE PLAN SHEET NOTES

 EXISTING WALLS SHOWN WITH NEW LIFE SAFETY RATINGS ARE TO BE UPGRADED TO THE NEW RATING. THE UPGRADING INCLUDES PROTECTING ALL OPENINGS IN THE PARTITION.

- 2. EXISTING DRAWINGS PROVIDED BY THE OWNER.

- i. ACCESSIBLE PATH OF TRAVEL AS INDICATED ON PLAN IS A BARRIER FREE ACCESS ROUTE WITHOUT ANY ABRUPT LEVEL CHANGES EXCEEDING 1/2" IF BEVELED AT 1:2 MAX SLOPE, OR VERTICAL LEVEL CHANGES NOT EXCEEDING 1/4" MAX. AND AT LEAST 48" IN WIDTH. SURFACE IS STABLE, FIRM, AND SLIP
- CROSS SLOPE DOES NOT EXCEED 2% AND SLOPE IN THE DIRECTION OF TRAVEL IS LESS THAN 5%, UNLESS OTHERWISE INDICATED. ACCESSIBLE PATH OF TRAVEL SHALL BE MAINTAINED FREE OF OBJECTS GREATER THAN 4" PROJECTION FROM WALL
- 6. ALL TEMPORARY EXITS SHALL BE APPROVED BY FIELD OSHPD FIRE MARSHALL AS WELL AS THE LOCAL FIRE MARSHALL PRIOR

FLOOR PLAN LEGEND

1. EXISTING PARTITION EXISTING 2 HR RATED PARTITION

3. NEW PARTITION 4. NOT IN SCOPE OF WORK

1-HR FIRE BARRIER

2-HR FIRE BARRIER

SHORING AREA / NEW CONSTRUCTION

CONSTRUCTION PHASING

NORTH EXIT STAIR CONSTRUCTION PHASING:

- . CONSTRUCT TEMPORARY RAMP AND EXIT PASSAGEWAY AS
- NOTED IN STAIR CONSTRUCTION PHASE 1 THIS SHEET. SEE SHEET 17A41-05 FOR MORE DETAILED INFORMATION.
- EXTERIOR WALLS, ADJUST EXTERIOR SITE WORK TO FINAL GRADE AS PER CIVIL PLANS. REFERENCE SHEET 17G00-04
- REMOVE TEMPORARY EXIT RAMP. REMOVE TEMPORARY EXIT PASSAGEWAY AND REVERT ROOM BACK TO PATIENT ROOM. REFERENCE SHEET 17A41-05A.

AUDITORIUM CONSTRUCTION PHASING:

- THIS PLAN. NOTE, THAT EXISTING EXITS TO EXTERIOR WILL BE MAINTAINED UNTIL THE NEW EXIT PASSAGEWAY IS COMPLETED AND APPROVED FOR OCCUPANCY BY OSHPD FIELD STAFF.
- CONCURENT WITH AUDITORIUM CONSTRUCTION. PROCEED WITH EXTERIOR SITE WORK FOR NEW WALKWAY, EMERGENCY



SITE UTILITY MAKE **READY PROJECT**

KEYPLAN

ISSUE CHART


G SITE-MAKEREADY-BKCHK #1 02/23/2018 F GMP #2 BID SET ADDENDUM #2 02/16/2018 TITLE


I SITE-MAKEREADY-BKCHK #2 6/08/2018

LEVEL 01 - INTERIM FIRE / LIFE SAFETY **EXIT PLAN**

SHEET NUMBER

17G00-03





SITE DEMOLITION GENERAL NOTES

- REFER TO SPECIFICATION FOR INTERIM LIFE SAFETY MEASURES AND REFER TO SHEETS 17G00-03 FOR EXISTING EGRESS/INTERIM LIFE SAFETY PLANS SHOWING INTERIM LIFE SAFETY AND PHASING SCOPE OF WORK
- 2. THESE DRAWINGS HAVE BEEN DEVELOPED FROM EXISTING DRAWINGS WHICH MAY NOT REFLECT ACTUAL FIELD CONDITIONS. VERIFY THESE DRAWINGS WITH EXISTING FIELD CONDITIONS AND NOTIFY THE ARCHITECT IMMEDIATELY IF INCONSISTENCIES BETWEEN THEM AND ACTUAL CONDITIONS BEFORE PROCEEDING WITH CONSTRUCTION
- REPAIR ANY DAMAGED FIRE RATED ASSEMBLIES TO THEIR ORIGINAL SPECIFICATION
- 4. WHERE NEW FINISHES ARE TO BE INSTALLED ON EXISTING SURFACES, REMOVE THE EXISTING FINISH AND PREPARE SURFACE TO RECEIVE THE
- 5. COORDINATE WITH THE OWNER ANY ITEMS TO BE STORED AND/OR
- 6. SEE CIVIL, MECHANICAL, PLUMBING, AND ELECTRICAL DRAWINGS FOR
- DEMOLITION OF UTILITIES.

 7. MAINTAIN EXIT EGRESS FOR ALL OCCUPIED AREAS OF THE BUILDING
- THROUGHOUT CONSTRUCTION AS SHOWN ON G00-03.
- 8. DEMOLITION WORK SHALL BE EXECUTED IN CONFORMANCE WITH ALL CODES AND AS SET FORTH BY ALL GOVERNING AUTHORITIES.
- BRACE ALL EXISTING STRUCTURES OF STRUCTURAL ELEMENTS AS NECESSARY DURING DEMOLITION.
- 10. DO NOT CUT ANY STRUCTURAL WORK WITHOUT PRIOR APPROVAL FROM THE STRUCTURAL ENGINEER.
- 11. THE EXISTING BUILDING ENVELOPE SHALL BE MAINTAINED IN A WATER TIGHT CONDITION AT ALL TIMES.
- 12. REPLACE OR REPAIR ANY EXISTING TO REMAIN FINISHES WHICH ARE DAMAGED DURING DEMOLITION.13. NOTIFY THE ARCHITECT IMMEDIATELY IF THE REMOVAL OF MECHANICAL,
- ELECTRICAL, PLUMBING SYSTEMS OR COMPONENTS WILL ADVERSELY AFFECT THE OPERATION OF MEP SYSTEMS OUTSIDE THE LIMITS OF DEMOLITION.
- 14. SCHEDULE ALL DEMOLITION WITH THE OWNER.

SITE DEMOLITION LEGEND

PROPERTY LINE

SCOPE OF WORK

EXTENT OF SITE DEMOLITION

(FOR DEMOLITION OF EXISTING



SITE DEMOLITION NOTES BY NUMBER

- EXISTING MODULAR BUILDINGS TO BE DEMOLISHED AND/OR REMOVED AS PART OF SEPARATE PROJECT.
- DEMO EXISTING EMERGENCY GENERATOR, PAD AND ENCLOSURE. CAP ALL UTILITIES SEE ELECTRICAL DEMO PLANS.
- (3) DEMO EXISTING CONCRETE WALKWAYS/CURBS.
- DEMOLISH AND REMOVE ALL CURBS AND REROUTE CURB DRAINS SEE PLUMBING PLANS FOR REROUTING.
 CONTRACTOR TO FIELD VERIFY LOCATIONS OF ALL CURB DRAINS AND ASSOCIATED PIPING PRIOR TO DEMOLITION.
- 5 DEMOLISH AND REMOVE EXISTING CANOPY AND STRUCTURE.
- 6 EXISTING TREES TO BE REMOVED. SEE SEPARATE CIVIL LADBS GRADING PACKAGE
- 7 REMOVE EXISTING DRAINAGE CHANNEL.
- PREPARE SITE FOR GRADING, EXCAVATION AND TEMPORARY SHORING SEE SHEET 17A01-02 FOR SHORING AREA AND SEE STRUCTURAL PLANS OSHPD PROJECT S172393-19-00 FOR TEMPORARY SHORING.



SITE UTILITY MAKE READY PROJECT

KEYPLAN

ISSUE CHART

 G
 SITE-MAKEREADY-BKCHK #1
 02/23/2018

 F
 GMP #2 BID SET ADDENDUM #2
 02/16/2018

 MARK
 ISSUE
 DATE

 Job Number
 715016

 Drawn
 Author


 Checked
 Checker

 Approved
 Approver

ENLARGED DEMOLITION SITE PLAN


SHEET NUMBER

17A01-01



OUTLINE OF TEMPORARY SHORING AND AREA FOR NEW PATIENT WING -(E) AUDITORIUM _.._. _..._..._.._ BUILDING 06

2 LEVEL 01 -ENLARGED FLOOR PLAN DEMO



SITE DEMOLITION GENERAL NOTES

DEMOLITION NOTES:

REFER TO SPECIFICATION FOR INTERIM LIFE SAFETY
 MEASURES AND REFER TO SHEETS 17G00-02 FOR EXISTING
 EGRESS/INTERIM LIFE SAFETY PLANS SHOWING INTERIM LIFE

- SAFETY AND PHASING SCOPE OF WORK

 2. THESE DRAWINGS HAVE BEEN DEVELOPED FROM EXISTING DRAWINGS WHICH MAY NOT REFLECT ACTUAL FIELD CONDITIONS. VERIFY THESE DRAWINGS WITH EXISTING FIELD CONDITIONS AND NOTIFY THE ARCHITECT IMMEDIATELY OF INCONSISTENCIES BETWEEN THEM AND ACTUAL CONDITIONS BEFORE PROCEEDING WITH CONSTRUCTION.
- 3. SEE CIVIL, MECHANICAL, PLUMBING, AND ELECTRICAL DRAWINGS FOR DEMOLITION OF UTILITIES..
- DRAWINGS FOR DEMOLITION OF UTILITIES..

 4. FOLLOW INFECTION CONTROL PROCEDURES OUTLINED IN SPECIFICATIONS TO MINIMIZE THE SPREAD OF DUST AND
- TYPICAL WALL REMOVAL INCLUDES FINISHES AND MECHANICAL, PLUMBING, ELECTRICAL, AND TELECOM SYSTEMS CONTAINED THEREIN. REMOVE DOORS, CASEWORK, WINDOWS, FRAMES AND OTHER FIXTURES, UNO.

5. REMOVE EXISTING CONSTRUCTION ONLY AS INDICATED.

- 6. MAINTAIN EXIT EGRESS FOR ALL OCCUPIED AREAS OF THE BUILDING THROUGHOUT CONSTRUCTION.
 7. DEMOLITION WORK SHALL BE EXECUTED IN CONFORMANCE
- WITH ALL CODES AS SET FORTH BY ALL GOVERNING AUTHORITIES.

 8. EXISTING BUILDING ENVELOPES SHALL BE MAINTAINED IN A
- WATER TIGHT CONDITION AT ALL TIMES.

 9. NOTIFY THE ARCHITECT IMMEDIATELY IF THE REMOVAL OF MECHANICAL, ELECTRICAL, PLUMBING, AND TELECOM
- SYSTEMS OR COMPONENTS WILL ADVERSELY AFFECT THE OPERATION OF SYSTEMS OUTSIDE THE LIMIT OF DEMOLITION.

 10. SCHEDULE ALL DEMOLITION WORK WITH OWNER PRIOR TO
- COMMENCEMENT.

 11. COORDINATE WITH THE OWNER ANY ITEMS TO BE STORED AND/OR RELOCATED.

RECONSTRUCTION NOTES: 1. REPAIR ANY OPENINGS OR FAULTS IN

1. REPAIR ANY OPENINGS OR FAULTS IN STRUCTURAL SYSTEMS PER DIRECTION OF STRUCTURAL ENGINEER. THESE INCLUDE BUT ARE NOT LIMITED TO, FLOOR CEILING ASSEMBLIES, STRUCTURAL COLUMNS AND BEAMS.

- 2. FILL OPENINGS OR GAPS CREATED IN FIRE- OR SMOKE-RATED ASSEMBLIES TO THEIR ORIGINAL RATING USING EQUIVALENT MATERIALS WHENEVER POSSIBLE, PREPARE FOR FINAL FINISH, UNO
- 3. BRING DISCOVERED EXISTING GAPS OR OPENINGS IN FIRE-RATED ASSEMBLIES TO THE ATTENTION OF THE ARCHITECT.
- 4. FILL OPENINGS OR GAPS CREATED IN NON-FIRE-RATED
 ASSEMBLY WITH EQUIVALENT MATERIALS WHENEVER
- POSSIBLE, PREPARE FOR FINAL FINISH, UNO

 5. WHERE NEW FINISHES ARE TO BE INSTALLED ON EXISTING
- SURFACES, REMOVE THE EXISTING FINISH AND PREPARE SURFACE TO RECEIVE THE NEW FINISH.

 6. COORDINATE WITH OWNER ANY ITEMS TO BE STORED AND/
- COORDINATE WITH OWNER ANY ITEMS TO BE STORED OR RELOCATED.
- 7. REPLACE OR REPAIR ANY EXISTING TO REMAIN FINISHES WHICH ARE DAMAGED DURING DEMOLITION (E.G. CEILING GRIDS, CEILING TILES, WALL COVERINGS, FLOOR FINISHES,



PROJECT

KEYPLAN

ISSUE CHART

PROVIDENCE

Medical Center

SITE UTILITY MAKE


READY PROJECT

Tarzana

SITE DEMOLITION LEGEND

PROPERTY LINE

SCOPE OF WORK



EXTENT OF DEMOLITION

SITE DEMOLITION NOTES BY NUMBER

- MAINTAIN FIRE AND SMOKE RATINGS OF ALL EXISTING WALLS TO REMAIN.
- PARTIALLY DEMO AND REMOVE EXISTING EXTERIOR STOREFRONT TO ACCOMMODATE NEW DOOR AND DOOR FRAME.
- DEMOLISH AND REMOVE EXISTING STAGE / PLATFORM, FRAMING, ACCESS RAMP AND STAIRS
- DEMOLISH AND REMOVE PORTION OF INTERIOR WALL AND FRAMING TO ACCOMODATE NEW DOOR OR CASED OPENING. PATCH AND REPAIR (E) WALL TO REMAIN AS REQUIRED TO MAINTAIN EXISTING FIRE RATING.
- 5 DEMOLISH AND REMOVE EXISITNG MILLWORK / CASEWORK.
- DEMOLISH AND REMOVE EXISITNG ACT CEILING AND GRID WHERE REQUIRED TO PERMIT NEW WALL ATTACHMENT TO STRUCTURE ABOVE.
- 7 DEMOLISH AND REMOVE PORTION OF RAILING TO ALLOW REQUIRED EXIT PATH CLEARANCE.
- COORDINATE WITH OWNER TO SECURE EXISTING EXIT DOOR
 NO LONGER IN USE. ENSURE THAT ALL (E) EXIT DOORS AND
 PATHWAYS ARE MAINTAINED IN OPERATION UNTIL THE
 ALTERNATIVE EXIT PASSAGEWAY ROUTE IS COMPLETED
- RELOCATE (E) DIFFUSERS &/OR CEILING FIXTURES ALIGNED WITH THE LOCATION OF NEW PARTITIONS WHERE REQUIRED TO ALIGH WITH C/L OF NEAREST ADJACENT CEILING TILE. CONTRACTOR TO VERIFY LOCATIONS OF ALL EXISTING CEILING FIXTURES AND EQUIPMENT PRIOR TO CONSTRUCTION.
- COMPLETELY REMOVE INTERIOR WALL INCLUDING ASSOCIATED MISCELLANEOUS ANCHORAGE/ATTACHMENTS, ELECTRICAL SEE ELECTRICAL PLANS FOR REROUTING.
- DEMOLISH AND REMOVE AREA OF GYP. BOARD CEILING AND FRAMING REROUTE AND/OR REMOVE ELECTRICAL, LIGHTING AND FIXTURES AS REQUIRED COORDINATE WITH OWNER. CAP ALL ELECTRICAL CONNECTIONS.
- REMOVE EXISTING DOOR.
- (13) REMOVE EXISTING RESILIENT FLOOR FINISH TO THE EXTENT SHOWN.
- REMOVE EXISTING WALL UP TO 8'-0" A.F.F. ADD GYP. AT NEW OPENING HEAD. PAINT TO MATC EXISTING ALL WALLS IN NEW CORRIDOR.

 REMOVE EXISTING CEILING KEEP EXISTING LIGHT FIXTURE TO REINSTALL IN NEW CEILING

 INSTALL TEMPORARY 2 HR RATED CONSTRUCTION BARRIER
 - COMPLETELY REMOVE INTERIOR WALL INCLUDING ASSOCIATED MISCELLANEOUS ANCHORAGE/ATTACHMENTS, ELECTRICAL SEE ELECTRICAL PLANS FOR REROUTING. MAINTAIN FIRE RATED INTEGRITY OF STAIR UNTIL THE CONSTRUCTION OF THE 2-HR RATED ENCLOSURE FOR DOOR W013 IS COMPLETE.

munimunimund

LEVEL 01 - ENLARGED DEMOLITION PLANS

SHEET NUMBER

17A04-01


Copyright © 2018 Perkins+Will

Approver

TITLE

1 LEVEL 01
1/8" = 1'-0"


1 LEVEL 01 - ENLARGED RCP DEMO




INTERIM 2HR EXIT PASSAGE

- ENLARGED RCP

1/8" = 1'-0" |





FLOOR PLAN SHEET NOTES

REFER TO GENERAL PROJECT NOTES FOR ADDITIONAL INFORMATION.

ASSEMBLIES TO REMAIN.

EXISTING DIMENSIONS ARE BASED ON EXISTING DRAWINGS AND ARE FOR REFERENCE ONLY. CONTRACTOR TO FIELD VERIFY ALL EXISITNG FIXTURES, COMPONENTS AND

PROTECT IN-PLACE ALL EXISTING FINISHES, FIXTURES AND ASSEMBLIES TO REMAIN.

SEE PROJECT INFORMATION SHEET FOR TYPICAL MOUNTING HEIGHTS OF ACCESSORIES, OUTLETS, SWITCHES, & LIFESAFETY FIXTURES.

ALL NEW PARTITIONS TO BE AS NOTED. REFER TO SHEET 17
A61-05 FOR PARTITION TYPE DETAILS. WHEN SCHEDULED
PARTITION IS TO RECEIVE DOUBLE LAYER OF GWB ON ONE
SIDE ONLY, DOUBLE LAYER TO BE LOCATED ON SIDE OF

ALL GWB COMPONENTS SHALL BE FROM ONE MFR AND LEVEL 4

ALIGN CENTERLINE OF PARTITION WITH CENTERLINE OF (E) MULLION OR COLUMN, WHERE REQUIRED, TYPICAL.

DOOR OPENING ARE LOCATIONED 6" FROM FINISHED FACE OF WALL (HINGE SIDE), UNO.

VERIFY ALL STRUCTURAL, MECHANICAL AND ELECTRICAL REQUIEMENTS AND COORDINATE REQUIRED CHANGES PRIOR TO CONSTRUCTION

EQUIPMENT AND FURNITURE SHOWN DASHED ARE NOT INCLUDED IN CONTRACT AND ARE FOR REFERENCE ONLY, UNLESS SPECIFICALLY NOTED

INSTALL SOUND BOOTS (MIN 1" THICK ACOUSTIC LINING) @ ALL OPENINGS IN SLAB TO ROOF DECK PARTITIONS AS REQ'D FOR RETURN AIR. REFER TO MECH DRAWINGS.

PROVIDE FIRE PROOFING BELOW DECK WHERE FLOOR BOX OR FLOOR PENETRATIONS OCCUR TO MAINTAIN FIRE RAITING REQUIREMENTS.

PROVIDE MINIMUM 1'-0" CLEAR FLOOR SPACE AT THE PUSH SIDE OF EVERY DOOR WITH A CLOSER. PROVIDE MINIMUM 1'-6" CLEAR AT THE PULL SIDE OF EVERY DOOR (EXCLUDING

PATIENT ROOMS) UNLESS SPCIFICALLY DIMENSIONED, NOTED

PROVIDE AIR BALANCE REPORT PRIOR TO PROCEEDING WITH ANY DEMOLITION OF THE (E) AUDITORIUM.



PROJECT

KEYPLAN

ISSUE CHART

PROVIDENCE

SITE UTILITY MAKE

READY PROJECT

Tarzana Medical Center

FLOOR PLAN LEGEND

1. EXISTING PARTITION

OR SHOWN OTHERWISE.

2. ——— EXISTING 2 HR RATED PARTITION

3. NEW PARTITION4. NOT IN SCOPE OF WORK

SMOKE PARTITI

SMOKE PARTITION

1-HR FIRE BARRIE

2-HR FIRE BARRIER

8. SHORING AREA / NEW CONSTRUCTION

NOTES BY NUMBER

OUTLINE OF TEMPORARY SHORING AND EXCAVATION AREA FOR NEW PATIENT WING- SEE STRUCTURAL PLANS OSHPD PROJECT S172393-19-00

(2) CHAIN LINK CONSTRUCTION FENCE

(3) INFILL / REPAIR GYP BOARD CEILING TO MATCH (E)

4 RE-INSTALL (E) RATED DOOR - REVERSE SWING

5 INSTALL EXTENSION TO HANDRAIL - MATCH (E), WRAP CASED OPENING

6 NEW FLOOR FINISH AND BASE

<u>.</u>

7 NEW RESILIENT BASE, TYP. AT NEW PARTITIONS.

8 NEW 2 HR RATED GYP BOARD TUNNEL CEILING, SEE DETAIL 7/ 17 A61-05.

(9) EGRESS LIGHTING ABOVE LANDING AND AT EXIT RAMP

(11) EXIT SIGN OVER DOOR - SEE ELECTRICAL PLANS

LIGHTING FIXTURE CENTERED IN CEILING - SEE ELECTRICAL


LEVEL 01 - ENLARGED PLANS

SHEET NUMBER

17A11-01

Copyright © 2018 Perkins+Will

TITLE



1 BDG 07 - LOWER ROOF PLAN

1/8" = 1'-0"

ROOF PLAN GENERAL NOTES

- 1. THESE DRAWINGS ARE DEVELOPED FROM EXISTING DRAWINGS WHICH MAY NOT REFLECT ACTUAL FIELD CONDITIONS. VERIFY ALL DIMENSIONS, LOCATIONS WITH ACTUAL FIELD CONDITIONS. NOTIFY ARCHITECT IMMEDIATELY OF ANY INCONSISTENCIES BEFORE PROCEEDING WITH CONSTRUCTION.
- 2. REFER TO MECHANICAL, PLUMBING AND ELECTRICAL FOR LOCATIONS OF PIPING, CURBS, VENTS, DUCTS, FANS AND OTHER ITEMS ON ROOF SURFACE.
- 3. (E) ROOFING SYSTEM TO REMAIN PROTECT IN PLACE ALL EXISTING ROOFTOP SURFACES, EQUIPMENT AND FIXTURES

ROOF PLAN LEGEND

ROOF DRAIN

SLOPE , 1/4" PER FOOT MIN FLOW TO DRAIN

NOT IN SCOPE OF WORK

WINDOW WASHING DAVIT

NOTES BY NUMBER

REROUTE ROOF AND OVERFLOW DRAINS - SEE PLUMBING PLANS.



PROJECT

PROVIDENCE

Tarzana

Medical Center

SITE UTILITY MAKE READY PROJECT

KEYPLAN


ISSUE CHART

b Number 715016
awn Author
ecked Checker
proved Approver

BDG 07 - PARTIAL ROOF PLAN

SHEET NUMBER

17A11-02B



ROOF PLAN GENERAL NOTES

- 1. THESE DRAWINGS ARE DEVELOPED FROM EXISTING DRAWINGS WHICH MAY NOT REFLECT ACTUAL FIELD CONDITIONS. VERIFY ALL DIMENSIONS, LOCATIONS WITH ACTUAL FIELD CONDITIONS. NOTIFY ARCHITECT IMMEDIATELY OF ANY INCONSISTENCIES BEFORE PROCEEDING WITH CONSTRUCTION.
- REFER TO MECHANICAL, PLUMBING AND ELECTRICAL FOR LOCATIONS OF PIPING, CURBS, VENTS, DUCTS, FANS AND OTHER ITEMS ON ROOF SURFACE.
- 3. (E) ROOFING SYSTEM TO REMAIN PROTECT IN PLACE ALL EXISTING ROOFTOP SURFACES, EQUIPMENT AND FIXTURES

ROOF PLAN LEGEND

00	ROOF DRAIN
SLOPE	SLOPE , 1/4" PER FOOT MIN FLOW TO DRAIN
0	WINDOW WASHING DAVIT
	NOT IN SCOPE OF WORK

NOTES BY NUMBER

REROUTE ROOF AND OVERFLOW DRAINS - SEE PLUMBING PLANS.



PROVIDENCE
Tarzana
Medical Center

SITE UTILITY MAKE READY PROJECT

KEYPLAN


ISSUE CHART


	TITLE
oproved	Approver
necked	Checker
rawn	Author
b Number	715016
ARK ISSUE	DATE


BDG 06 - PARTIAL ROOF PLAN

SHEET NUMBER

17A11-03B









PROJECT PROVIDENCE Medical Center SITE UTILITY MAKE **READY PROJECT**

KEYPLAN


ISSUE CHART


I SITE-MAKEREADY-BKCHK #2 6/08/2018 G SITE-MAKEREADY-BKCHK #1 02/23/2018 F GMP #2 BID SET ADDENDUM #2 02/16/2018 Job Number 715016 Author Checker Approver TITLE


DETAILS

SHEET NUMBER

17A61-06







715016 Approver

